

Grants by Grant Cycle

Grants matching your search for 2007-08 *Rubberized Asphalt Concrete Grants (RAC10)*

Los Angeles County

Grantee: City of Glendale

Amount Awarded: \$48,250.00

Grantee Contact: Dennis Ambayec

Grantee Contact Phone Number: 818-548-3945

CalRecycle Grant manager: Victoria Rocha

Project Summary: Project 1:

Loc.: Glenoaks Blvd Rehabilitation Proj.

Limits: Grandview Ave to Westerly City Boundary

Length: 6,780`

Width: 96`

Depth: Approx. 1.5`

Tons of RAC Used: 6,300

Amt. of crumb rubber: 18% +/- 2% crumb rubber modifier , approx. 27 lbs. per ton of RAC

Start/Completion Dates:
January 2008 to June 2008

Proj. 2:

Loc.: Piedmont Ave Rehab. Proj.

Limits: Ramsdell Ave to La Crescenta Ave

Length: 1,500`

Width: 36`

Depth: 1.5`

Tons of RAC Used: 550

Amt. of crumb rubber per ton of RAC:
same

Start/end date: July 2008 - Oct. 2008

Proj. 3:

Loc.: Los Feliz Rd Rehab. Proj.

Limits: Westerly City Boundary to Central Ave

Length: 1,362`

Width: 73`

Depth: 1.5

Tons of RAC used: 1,000

Amt. of crumb rubber: same

Start/end dates: July 2008 - Oct. 2008

Proj. 4:

Loc.: Verdugo Rd Rehab. Proj.

Limits: LaCanada Blvd (Northerly Wye) to LaCrescenta Ave

Length : 1,900`

Width: 82`

Depth: 1.5`

Tons of RAC used: 1,800

Amt. of crumb rubber: same

Start/end dates: July 2008 - Oct. 2008

Grantee: Los Angeles County

Amount Awarded: \$250,000.00

Grantee Contact: Karen Steinhoff

Grantee Contact Phone Number:

CalRecycle Grant manager: Victoria Rocha

Project Summary: Project 1:

Loc.: Unincorporated LA County area of Hacienda Heights: Hacienda Blvd

Limits: Richview Drive to 550` s/o Glenmark Drive

Type of RAC: Asphalt Rubber

Length: 2`

Tons of RAC used: 1,279

Amt. of crumb rubber: 20.9 lbs/ton

Start/end dates: 7/08 - 10/08

Project 2:

Loc.: Unincorporated LA County area of Rowland Heights: Fullerton Rd

Limits: Senteno St to Pathfinder Rd

Length: 2,970`

Width: 80`

Depth: 1.5`

Tons of RAC used: 2,227

Amt. of crumb rubber: 20.9 lbs/ton

Start/end dates: 4/08 - 7/08

Project 3:

Location: Unincorporated LA County area of Rosewood: Figueroa St, Et Al.

Limits: Alondra Blvd to 800` N/O Compton Blvd; and various other streets

Type of RAC: Asphalt-Rubber

Length: 3,900`

Width: 50`

Depth: 2.5`

Tons of RAC Used: 3,041

Amt. of crumb rubber: 20.9 lbs/ton

Start/end dates: 8/08 - 10/09

Proj. 4:

Unincorporated LA County area of Soledad; Soledad Canyon Rd

Limit: 2855` W/O County Mile Marker 1507

Type of RAC: Asphalt-Rubber

Length: 25,400`

Width: 24`

Depth: 1.5

Tons of RAC Used: 5,725

Amt. of crumb rubber: 20.9 lbs/ton

Starting/end dates: 9/08 - 4/09

Proj 5:

Loc.: Unincorporated LA County near Arcadia; Mountain Ave

Limits: 80` S/O Lewiston St to 760` S/O Camino Real

Type of RAC: Asphalt-Rubber

Length: 3,400`

Width: 52`

Depth: 1.5`

Tons of RAC Used: 1,653

Amt. of crumb rubber: 20.9 lbs/ton

Starting/End dates: 9/08 - 3/09

Proj 6:

Loc.: Unincorporated LA County near Malibu Lake; Mulholland Highway, Et Al.

Limits: Westlake Blvd to County Mile Marker 17.27; and various other streets

Type of RAC: Asphalt-Rubber

Length: 22,000`

Width: 28`

Depth: 2`

Tons of RAC Used: 7,722

Amt. of crumb rubber: 20.9 lbs/ton

Start/end dates: 5/09 - 3/10

Proj. 7:

Loc.: Unincorporated LA County area of Avocado Heights; Workman Mill Rd

Limits: Oaklman Drive to Valley Blvd

Type of RAC: Asphalt-Rubber

Length: 5,700`

Width: 64`

Depth: 1.5`

Tons of RAC: 3,425

Amt. of crumb rubber: 20.9 lbs/ton

Starting/End dates: 9/08 - 5/09

Proj. 8:

Loc.: Unincorporated LA County area near Arcadia; Rosemead Blvd

Limits: Foothill Blvd to 566` S/O Ardenale Ave; and various other streets

Type of RAC: Asphalt-Rubber

Width: 60`

Depth: 2`

Tons of RAC Used: 2,038

Amt. of crumb rubber: 20.9 lbs/ton

Starting/end Dates: 4/09 - 2/10

Proj. 10:

Loc.: Unincorporated LA County area near Monte Nido; Schueren Rd

Limits: Piuma Rd to Saddle Peak Rd

Type of RAC: Asphalt-Rubber

Length: 9,700`

Width: 22`

Depth: 1.5`

Tons of RAC Used: 2,000

Amt. of crumb rubber: 20.9 lbs/ton

Starting/end Dates: 8/09 - 2/10

Proj. 11:

Unincorporated LA County area around Palmdale; Godde Hill Rd, Et Al.

Limits: 11345` N/O Elizabeth Lake Rd to Elizabeth Lake Rd; and various other streets

Type of RAC: Asphalt-Rubber

Length: 10,660`

Width: 36`

Depth: 2`

Tons of RAC Used: 4,796

Amt. of crumb rubber: 20.9 lbs/ton

Start/End dates: 6/08 - 6/09

Proj. 12:

Loc.: Unincorporated LA County area of Rancho Dominguez; Santa Fe Ave Et Al

Limits: Del Amo Blvd to 1200 S Alameda Street East; and various other streets

Type of RAC: Asphalt-Rubber

Length: 6,060`

Width: 72`

Depth: 2.5`

Tons of RAC Used: 6,817

Amt. of crumb rubber: 20.9 lbs/ton

Start/End Dates: 6/08 - 6/09

Proj. 13:

Unincorporated LA County area of Bouquet Canyon; Vasquez Canyon Rd

Limits: Bouquet Canyon Rd to Sierra Highway

Type of RAC: Asphalt-Rubber

Length: 19,000`

Width: 24`

Depth: 1.5`

Tons of RAC Used: 4,277

Amt. of crumb rubber: 20.9 lbs/ton

Start/End Dates: 5/08 - 10/09

Sacramento County

Grantee: City of Rancho Cordova

Amount Awarded: \$46,000.00

Grantee Contact: Brit Snipes

Grantee Contact Phone Number: 916-851-8905

CalRecycle Grant manager: Pamela Kelley

Project Summary: Project 1:

Loc.: Rancho Cordova

Limits: Coloma Rd from Folsom Blvd to McGregor Drive

Length: 1.8 mi

Width: 70` to 56`

Depth: 2` overlay of existing road section

Tons of RAC Used: 8,280

Amt. of crumb rubber: The asphalt-rubber mixture shall contain between 14 and 20 percent rubber by weight of the total asphalt-rubber mixture.

Construction Starting and Completion Dates:

August 30, 2007 to October 31, 2007

Project 2:

Location: Rancho Cordova

Limits: The intersection of Mather Field Blvd and Rockingham Dr.

Length: 240`

Width: 105`

Depth: 2` overlay of existing road section

Tons of RAC used: 368

Amt. of crumb rubber: The asphalt-rubber mixture shall contain between 14 and 20% rubber by weight of the total asphalt-rubber mixture.

Starting and Completion dates:

July 30, 2007 to October 31, 2007

Project 3:

Location: Rancho Cordova

Limits: The intersection of Old Placerville Rd and Rockingham Dr.

Length: 270`

Width: 54`

Depth: 2` overlay of existing road section

Tons of RAC used: 184

Amt. of crumb rubber: The asphalt-rubber mixture shall contain between 14 and 20% rubber by weight of the total asphalt-rubber mixture.

Project 4:

Location: Rancho Cordova

Limits: Mather Field Rd South of International Dr.

Length: 485`

Width: 54`

Depth: 2` overlay of existing road section

Tons of RAC used: 368

Amt. of crumb rubber: The asphalt-rubber mixture shall contain between 14 and 20% rubber by weight of the total asphalt-rubber mixture.

Starting and Completion Dates:

July 30, 2007 to October 31, 2007

Ventura County

Grantee: City of Moorpark

Amount Awarded: \$57,500.00

Grantee Contact: Dave Klotzle
Grantee Contact Phone Number: 805-517-6285
CalRecycle Grant manager: Victoria Rocha
Project Summary: Proj. #1:

Loc.: Tierra Rejada Rd.
Limits: Los Angeles Ave (SR-118) to Hidden Pines Rd
Length: 11,000`
Width: varies - 60 - 70`
Depth: 2`
Tons of RAC Used: 10,500
Amt. of crumb rubber: 32 lbs
Starting/Completion Dates:
October 2007 - December 2007

Proj. #2:
Loc.: Second St
Limits: Spring Rd o Moorpark Ave
Length: 2,100`
Width: 40`
Depth: 2`
Tons of RAC Used: 1,000
Amt. of crumb rubber: 32 lbs
Starting/Completion Dates:
October 2007 - December 2007

Total Awarded for County:\$57,500.00

| | |
|-----------------------|--|
| Grant Count: 4 | Grand Total for Selected Counties: \$401,750.00 |
|-----------------------|--|