

Grants by Grant Cycle

Grants matching your search for **2007-08 Rubberized Asphalt Concrete Grants (RAC12)**

Alameda County

Grantee: City of Fremont

Amount Awarded: \$45,500.00

Grantee Contact: Mr. Jayson Imai

Grantee Contact Phone Number: 510-494-4732

CalRecycle Grant manager: Pamela Kelley

Project Summary: Proj. 1:

Location w/ limits:

Coco Palm Dr (Royal Palm Dr to Sundale Dr)

Farwell Dr (Mowry Ave to Flamingo Ln)

Mattos Dr (Fremont Blvd to Kimbro St)

Oak St (Thornton Ave to Alder Ave)

Sundale Dr (Logan Dr to 149 ft. South of Nelson St)

Walnut Ave (E/B) (Liberty St to Paseo Padre Parkway)

Walnut Ave (W/B) (Paseo Padre Parkway to Liberty St)

Construction starting and completion dates: 7/1/08 - 10/1/08

Type of RAC: Asphalt-Rubber

Amt. of crumb rubber:

(20% crumb rubber in binder) X (8% binder in mix) X 2,000 lb/ton =
32 lb of rubber per ton of RAC

Length: 12,700`

Width: 733`

Depth: 2` - 4`

Amt. of RAC: 9,100

X

Reimbursement Rate: \$5.00

Total: \$45,500

Total Awarded for County:\$45,500.00

Los Angeles County

Grantee: City of Santa Clarita

Amount Awarded: \$100,000.00

Grantee Contact: William Whitlatch

Grantee Contact Phone Number: 661-255-4933

CalRecycle Grant manager: Victoria Rocha

Project Summary: Project 1:

OL1 - John Russel Dr (Estaban Dr to Alicante Dr)
OL 2 - Magic Mtn. Pkwy (Valencia Blvd to Citrus St)
OL3 - Placerita Cyn Rd. (Sierra Hwy to Private Gate)
OL4 - Rockwell Canyon Rd (Valencia Blvd to McBean Pkwy)
OL5 - Valencia Blvd (Magic Mtn. Pkwy to Citrus St)
OL6 - Maple St 9 (Valley St to Cross St)
OL7 - Alicante Dr (Alta Madera Dr to John Russel Dr [Alternate])
OL8 - Cortina Dr (Alta Madera Dr to John Russel [Alternate])
OL9 - Langside Ave (Soledad Cyn Rd to Delight St [Alternate])
OL10 - Poppy Meadow St (Oleander Ct to Wisteria Valley Rd [Alternate])
OL11 - Valencia Blvd - McBean Pkwy to Citrus St [Alternate])

Grantee: City of Santa Monica

Amount Awarded: \$100,000.00

Grantee Contact: Margaret Talamantes

Grantee Contact Phone Number: 310-458-8721

CalRecycle Grant manager: Victoria Rocha

Project Summary: Project 1

Location & Limits: 2008 / 2009 City - Wide Street Improvement Project

Limits: City-wide (within City of Santa Monica)

Construction dates: 1/1/09 - 12/31/09

Type of RAC: Asphalt-Rubber

Amount of Crumb Rubber: 30,000

Length of Paving: 8.9 Miles

Width: Varies

Depth: 1-1/2` (Various)

Amount of RAC used: 20,000

Reimbursement Rate: \$5.00

Total: \$100,000

Total Awarded for County:\$200,000.00

Orange County

Grantee: City of Laguna Woods

Amount Awarded: \$68,760.00

Grantee Contact: Mr. Douglas C. Reilly

Grantee Contact Phone Number: 949-639-0561

CalRecycle Grant manager: Victoria Rocha

Project Summary: Proj. #1:

Loc. w/limits: El Toro Rd (City limits east to Moulton Pkwy)

Construction starting/completion dates: FY 2009/10

Type of RAC: Asphalt-Rubber

Amt. of crumb rubber: 141lbs/ton

Length: 8,875.71`

Width: 40`

Depth: .20`

Amt. of RAC Used: 5006

X

Reimbursement Rate: \$5.00

=

Total: \$25,030

Proj. #2:

Loc. w/limits: Moulton Parkway

(Phase 1 - Via Campo Verde to Santa Maria Ave)

(Phase 2 - Santa Maria Ave to Ridge Route)

Construction starting/completion dates: FY 2009/10

Type of RAC: Asphalt-Rubber

Amt. of crumb rubber: 141lbs/ton

Length:

Phase 1 - 4341.08`

Phase 2 - 394.11`

Width:

Phase 1 - 40`

Phase 2 - 18.44`

Depth:

Phase 1 - .20`

Phase 2 - .20`

Amt. of RAC Used: 2,550

X

Reimbursement Rate: \$5.00

=

Total: \$12,750

Proj. #3:

Loc. w/limits: Santa Maria Ave

Phase 1 - Terminus to approx 900` west of Via vista

Phase 2 - Via Vista to Moulton Parkway

Construction starting/completion dates: FY 2009/10

Type of RAC: Asphalt-Rubber

Amt. of crumb rubber: 141lbs/ton

Length:

Phase 1 - 2,968.98`

Phase 2 - 2,262.40`

Width:

Phase 1 - 84`

Phase 2 - 84`

Depth:
Phase 1 & 2 - .20`

Amt. of RAC Used: 6,196
X
Reimbursement Rate: \$5.00
=
Total: \$30,980

Total Awarded for County:\$68,760.00

Riverside County

Grantee: City of Riverside

Amount Awarded: \$63,500.00

Grantee Contact: Ibrahim Massoud

Grantee Contact Phone Number: 951-826-5805

CalRecycle Grant manager: Victoria Rocha

Project Summary: Proj. 1:

Loc. w/limits: Miscellaneous Street Rehab - Phase II (various streets)

Begin Construction April 2008; Complete Construction June 2008

Type of RAC: Asphalt-Rubber

Amt. of crumb rubber:
a ton of RAC mix contains 20% and 7.1 binder by weight of aggregate, then a ton of RAC mix (binder and aggregate) would contain 1.4% (20% x 7.1%) or 28 lbs. (1.4% x 2,000 lbs) of binder. (Sec. 203-114 of standard specification for public works construction, 2003 edition).

Amt. of RAC used: 7,200

Reimbursement rate: \$5.00

Total: 36,000

Proj. 2:

Loc. w/limits: Orange Terrace Parkway (Trautwein Rd to Van Buren Blvd)

Construction begins May 2008
Complete construction July 2008

Type of RAC: Asphalt-Rubber

Amt. of crumb rubber:
a ton of RAC mix contains 20% and 7.1 binder by weight of aggregate, then a ton of RAC mix (binder and aggregate) would contain 1.4% (20% x 7.1%) or 28 lbs. (1.4% x 2,000 lbs) of binder. (Sec. 203-114 of standard specification for public works construction, 2003 edition).

Amt. of RAC used: 5,500

Reimbursement rate: \$5.00

Total: 27,500.00

Total Awarded for County:\$63,500.00

Santa Barbara County

Grantee: City of Lompoc

Amount Awarded: \$58,000.00

Grantee Contact: Craig Dierling

Grantee Contact Phone Number: 805-875-8224

CalRecycle Grant manager: Victoria Rocha

Project Summary: Proj. 1:

Location w/ limits: A Street (Chestnut Ave to Ocean Ave)

Starting/Completion Dates:

June - Sept. 2008

Type of RAC: Asphalt-Rubber

Type of crumb rubber: 21-27 lbs per ton depending on approved mix design

Length: .23 mi

Width: varies from 52-64`

Depth: .20`

Amt. of RAC: 1,200

Reimbursement Rate: \$5

Total: \$6,000

Proj. 2:

Location w/ limits: Barton Ave (Honeysuckle Way to O St, H St to D St)

Starting/Completion Dates:

June - Sept 2008

Type of RAC: Asphalt-Rubber

Type of crumb rubber: 21-27 lbs per ton depending on approved mix design

Length: .38 mi

Width: varies 40-46`

Depth: .20`

Amt. of RAC: 1,400

Reimbursement Rate: \$5

Total: \$7,000

Proj. 3:

Location w/ limits: Central Ave (O St to H St, H St to D St)

Starting/Completion Dates:

June - Sept 2008

Type of RAC: Asphalt-Rubber

Type of crumb rubber: 21-27 lbs per ton depending on approved mix design

Length: .75 mi

Width: 68-72`

Depth: .20`

Amt. of RAC: 4,200

Reimbursement Rate: \$5

Total: \$21,000

Proj. 4:

Location w/ limits: College Ave (I St to H st, H St to D St, D St to A St, A St to 3rd)

Starting/Completion Dates:

June - Sept 2008

Type of RAC: Asphalt-Rubber

Type of crumb rubber: 21-27 lbs per ton depending on approved mix design

Length: .78 mi

Width: varies 44 - 55`

Depth: .20`

Amt. of RAC: 3,400

Reimbursement Rate: \$5

Total: \$17,000

Proj. 5:

Location w/ limits: O St (Central Ave to Aviation Dr, North Ave to Oak Ave)

Starting/Completion Dates:

June - Sept 2008

Type of RAC: Asphalt-Rubber

Type of crumb rubber: 21-27 lbs per ton depending on approved mix design

Length: .27 mi

Width: varies 46 - 64`

Depth: .20`

Amt. of RAC: 1,400

Reimbursement Rate: \$5

Total: \$7,000

Total Awarded for County:\$58,000.00

Grant Count: 6

Grand Total for Selected Counties: \$435,760.00

