

Grants by Grant Cycle

Grants matching your search for 2007-08 Targeted Rubberized Asphalt Concrete Incentive Grant Program (TRI23)

San Bernardino County

Grantee: City of Colton

Amount Awarded: \$134,000.00

Grantee Contact: Maritza Tapia

Grantee Contact Phone Number: 909-370-5065

CalRecycle Grant manager: Victoria Rocha

Project Summary: Proj. #1:

Loc. w/limits: Agua Mansa Rd (16+00 to 63+00)

Length: 6,600 ft

Width: 78`

Depth 4`

Tons of RAC: 6,200

Proposed Construction Start Date:
Jan 2010

Material Cost Info:

Historical Cost

Conventional AC: \$65/ton

Asphalt Rubber: \$85/ton

Testing Cost Info:

Historical Cost

Deflection Testing: \$5,000

QA/QC Testing: \$5,000

Amt. of RAC: 6,200

X

Diff. Cost of RAC: \$20

+

Testing Cost: \$10,000

=

Total: \$134,000

Total Awarded for County:\$134,000.00

San Joaquin County

Grantee: City of Tracy

Amount Awarded: \$83,400.00

Grantee Contact: Zabih Zaca

Grantee Contact Phone Number: 209-831-6452

CalRecycle Grant manager: Pamela Kelley

Project Summary: Location:
various locations within Tracy city limits (FY 2008 Overlay Project)

Limits:
Wilson (12th-Eaton);
Lincoln (Lowell-Grant Line);
Tracy (Valpico-Sycamore);
Linne (Corral Hollow-Tracy)
Holly Drive (Laguna-Larch)

Length:
1,000`;
2,400`;
2,100`;
5,500`
1,850` (respectively)

Width:
36`;
64`;
32`;
24`
42` (respectively)

Depth:
1.5`

Tons of RAC Used:
4,170

Proposed Construction Start Date:
May 2008

Material Cost Info:
Historical and Bid

Conventional AC \$90/ton (August 2006 bid)
Asphalt Rubber \$110/ton (August 2006 bid)

Calculation for Requested Amount:
Amt. of RAC: 4,170
X
Differential cost of RAC: \$20

Testing cost: 0

Total: \$83,400

Grantee: San Joaquin County

Amount Awarded: \$175,000.00

Grantee Contact: Peter D. Martin

Grantee Contact Phone Number: 209-468-3036

CalRecycle Grant manager: Pamela Kelley

Project Summary: Proj. 1:

Loc. w/ limits: Stockton, Wilson Way (Orwood Street to the Diverting Canal)

Length: 4,224 lf

Width: varies (72 - 84 lf) total area = 41,111 square yards

Depth: .12` of overlay

Tons of RAC Used: 3,504

Material Cost Info:
Historical Cost
Conventional AC: \$65/ton
Asphalt Rubber: \$125/ton

Testing Cost Info:
Historical Cost
Deflection Testing: \$0
QA/QC Testing: \$8,000

Amt. of RAC: 3,504
x
Diff Cost: \$60
+
Testing Cost: \$8,000
Total: \$218,240

Total Awarded for County:\$258,400.00

Grant Count: 3	Grand Total for Selected Counties: \$392,400.00
-----------------------	--