



Grants by Grant Cycle

Grants matching your search for 2016-17 Tire-Derived Aggregate Grant Program (TDA6)

Marin County**Grantee:**Marin County**Amount Awarded:** \$102,492.00**Grantee Contact:** John Berg**CalRecycle Grant Manager:** Loreto Tamondong

Project Summary: CalRecycle has edited the following summary to reflect the approved grant project: Marin County is proposing to use Tire-Derived Aggregate (TDA) in lieu of structural soil for fill behind a retaining wall in the construction and realignment of a roadway curve. An estimated 1,013.25 tons of TDA (equivalent to 101,325 PTEs) is anticipated to be installed from October 2017 through September 2018.

*Total Awarded for County: \$102,492.00***Mendocino County****Grantee:**City of Ukiah**Amount Awarded:** \$48,875.00**Grantee Contact:** Richard Seanor**CalRecycle Grant Manager:** Victoria Rocha

Project Summary: CalRecycle has edited the following summary to reflect the approved grant project: The City of Ukiah is reconstructing approximately 2,300 feet of a 4 lane (60 ft wide) arterial roadway. The Regional Water Quality Control Board requires all roadway reconstruction projects to implement Low Impact Development (LID) storm water capture and treatment systems. The City proposes to utilize underground bioretention swales adjacent to the roadway to meet the LID requirements. The permeable material proposed for the bioretention swales is Tire-Derived Aggregate (TDA). Approximately 600 tons of TDA (equivalent to 60,000 PTEs) is required to achieve the water volume capture requirements. Construction to start May 2017 through October 2017.

*Total Awarded for County: \$48,875.00***Stanislaus County****Grantee:**Stanislaus County**Amount Awarded:** \$35,733.00**Grantee Contact:** Peter Song**CalRecycle Grant Manager:** Farrah Fadrigon

Project Summary: CalRecycle has edited the following summary to reflect the approved grant project: The County proposes to use Tire-Derived Aggregate (TDA) as bottom fill for roadside horizontal drains at various locations in the County. The TDA will be covered with three feet of drain rock. An estimated 506 tons of TDA (equivalent to 50,625 PTEs) is anticipated to be installed from August 2017 through September 2017.

*Total Awarded for County: \$35,733.00***Grant Count: 3****Grant Total for Selected Counties: \$187,100.00**