



Landfill Redevelopment

Partnerships and Processes



LEA  **CIWMB**
PARTNERSHIP CONFERENCE
CATCHING THE WAVE OF COOPERATION
August 1-3, 2006 • Monterey, California



Former Palm Springs Landfill



THE SOURCE GROUP, INC.



Former Palm Springs Landfill



**THE
SOURCE GROUP, INC.**



View Toward Northwest

Former Palm Springs Landfill



**THE
SOURCE GROUP, INC.**



View Toward West

Palm Springs Brownfield Highlights

- **36.6-Acre Municipal Landfill**
- **Split Ownership (City & Private)**
- **Active from Early 1930's to Mid 1960's**
- **Vacant Since Mid-1960's**
- **Refuse Reduced in Burn Pits**




Palm Springs Brownfield Highlights

- **Sewage Treatment Operations in Southern Portion of Site**
- **Some Hazardous Materials**
- **Remediated/Developed without Public Money**
- **Unmaintained and Potentially Dangerous**



Palm Springs Brownfield Highlights

- **Unique Geotechnical Problems**
- **Complex Air Resource Issues**
- **Voluntary Cleanup Agreement w/DTSC**
- **Expedited Remediation**
- **Public Participation and Support**




Is it Possible?



THE SOURCE GROUP, INC.



Palm Springs Brownfield Site Redevelopment



- Economic Evaluation
- Lead Oversight Agency?
- Remedial Investigation Complete?
- Remediation & Redevelopment Plan
[Removal Action Workplan]

- Removal Action Implementation
- Development Considerations
- Financial Considerations
- Responsibilities
- Redevelopment

- Elements:
 - What is the "Clean" Land Value?
 - Environmental Liabilities
 - Cost
 - Intangibles
 - Development Costs
 - Funding / Financing / Economy
 - Insurance
 - Future Land Use
 - Risk Factors & Contingencies

- Selection Criteria:
 - Authority to Oversee Project
 - Technical Understanding
 - Support Redevelopment
 - Staff Availability
 - Existing Mechanism for Cost Reimbursement
 - Team Player
 - Cooperative / Helpful



- Defined SOW and Budget w/DTSC
- Iterative Feasibility Evaluation with DTSC
 - Environmental
 - Economics
 - Geotechnical
 - Public
- Landfill Material Required to Stay Within Existing Footprint

- Air Emissions
 - Heavy Equipment: Scrapers Fitted with Catalytic Converters to Maintain $\text{NO}_x < 100 \text{ lb/day}$.
 - Fugitive Emissions
- Landfill Excavation and Replacement
- Weather Conditions
- Dust Control
- Landfill Gas Collection System

- Contingencies for Management of Potentially Hazardous Materials
- Contingencies for Management of Potential Chemical Agent Identification Sets
- Health & Safety & PPE
- Long Term Monitoring

➤ Future Land Use:

- Land Value
- Geotechnical
- Tennant Requirements
- Mitigations
- Land Use Restrictions / Deed Restrictions
- Long-Term Liability




- 
- Former Palm Springs Landfill
 - City of Commerce Landfill
 - Cemetery Expansion – Palos Verdes

Former Palm Springs Landfill


- Landfill with depths from 3 to 23 feet.
- Removed and consolidated over 600,000 cy of landfill material.
- Excavated and compacted over 400,000 cy of clean soil, including a 3-foot "clean" cap.
- Landfill material consolidated in deed restricted area in the center of the property with 400,000 sf shopping center around perimeter.
- Key to success was accurate prediction of blended landfill material.
- Landfill/native interface visually obvious allowing productive excavation.
- Lead main contaminant of concern with no migration below landfill native interface.
- Had to Modify Cell Configuration During Project.



City of Commerce Landfill



Cemetery Expansion – Palos Verdes



Cemetery Expansion – Palos Verdes

- Former Rock Quarry Filled with Approximately 150,000 cy of Steel Producing By-Products Including Foundry Sand, Slag and Baghouse Dust.
- Landfill Consolidated into Smaller and Deeper area with Liners Below and Above Material.
- Eight ft of Clean Soil Above Landfilled Material for Double-Level Caskets and Turf.
- Extremely Strict Clean Up Levels Required by Cemetery Management.
- Lead was the Primary Contaminant of Concern.
- Landfill/Native Interface Visually Obvious Allowing Productive Excavation.
- Lead Did Not Migrate Below Landfill/Native Interface.

