

GENERAL OUTLINE FOR:

Construction And Demolition Waste Management

Goal:

Divert 75% by weight

Waste Management Plan:

Indicate how to achieve diversion Goal

Compliance with section "Quality Assurance"

List facilities receiving recycling materials

Describe process and list organizations receiving the reusable materials

Identify materials to be disposed and explain why they are not recovered

List landfill or facilities to receive the disposal materials

Indicate barriers to recycling in the project

List reuse and recyclable materials, and estimate their amount by weight

Estimate time required for demolition/deconstruction

Prepare building survey and worker safety plan

Provide site management plan

Provide final accounting of recovered materials for final payment

Waste Management Summary Reports:

Information of facility

Information of material received

Cost / Saving

Progress Payment:

Submit approved Waste Management Summary Report

Prepare rebate information

Payment depends on meeting diversion goal

Incentive for recycling every 5 % above diversion goal

Quality Assurance:

Regulatory Requirements

Permitted facilities

Pre-C&D Waste Management Meeting

Plan Revision

Implementation

Records keeping

Storage and Handling:

Removal of material from site
Security for recovered materials
Proper handling of recovered materials

Project Conditions:

Noise
Erosion control
Measures for common hazardous materials
Labeling
Site plan requirements

Products:

List of reusable materials
List of recyclable materials